KOLAR DISTRICT.

Abstract Notification, dated 17th February 1936.

The attention of the public is invited to the notification on pages 257-258, Part VI of the *Mysore Gazette*, dated 20th February 1936, inviting tenders for the work of improvements to the feeder channel of Bodimarlur tank Register No. 164, Goribidnur Taluk.

The last date for the receipt of tender is 2 P.M. on the 16th March 1936.

Abstract Notification dated 15th February 1936.

The attention of the public is invited to the Notification in pages 290 to 299 of the issue of *Mysore Gazette*, dated 27th February 1936, calling for tenders for the work of (i) constructing a new masonry weir at the right end in place of the damaged weir and closing the breach of Thimmapalli Kanavekere, Register No. 858, Bagepalli Taluk, (ii) Restoring Balareddipalli Gurammanakere, Register No. 635, Bagepalli Taluk, (iii) Filling the breach and extending the weirs at both flanks of Maddepalli Doddakere, Register No. 860, Bagepalli Taluk, (iv) Restoring Bagepalli Voddu, Register No. 639, Bagepalli Taluk, (v) Restoring Muthakapalli Dodkere, Register No. 788, Bagepalli Taluk. The last date for receipt of tender is 16th March 1936.

N. SUBBA RAO,
Executive Engineer.

SHIMOGA DIVISION.

Abstract Notification dated 24th February 1936.

The attention of the public is invited to the advertisement in pages 299-232 of the *Mysore Gazette*, dated 27th February 1936, calling for tenders for " Renovating the Old Jail Buildings at Shimoga".

Each tender must be accompanied by a Treasury challan for having deposited Rs. 300 as earnest money.

The work should be completed by the end of December 1936 with a monthly progress of Rs. 2,000.

Abstract Notification, dated 18th February 1936.

The attention of the public is invited to the advertisement in pages 303-304 of the *Mysore Gazette*, dated 27th February 1936 calling for tenders for " Repairing the Basankatte of Shivanathankoppa Doddakere, Register No. 341, of Shikarpur Taluk.

Each tender must be accompanied by a Treasury Challen for having deposited Rs. 150 as earnest money.

The work should be completed by the end of March 1936 (with a monthly progress of not less than Rs. 1,500), failing which a penalty of Rs. 100 per week will be levied.

The last date for receiving tenders is 2 P.M., on Monday the 9th March 1936.

B. KRISHNA RAO,
Executive Engineer.

CHITALDRUG DIVISION.

Notification dated 25th February 1936.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Chitaldrug Division, up to 2 P.M., on 13th March 1936, for constructing two Blocks of Six Units each of Police Lines and one quarters for non-commissioned officer at Davangere. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1936.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Chitaldrug between the hours of 11 A.M. and 5 P.M. on working days.

3. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed both in words and figures. The work will be distributed to two tenderers for speedy execution of work.

4. Each tender must be accompanied by a deposit of Rupees four hundred and fifty (Rs. 450) in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for constructing 2 Blocks of Six Units of Police Lines and one quarters for non-Commissioned Officer at Davangere" in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitors, whose tenders have been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of two of the tenders, the earnest money on rejected tenders, will be returned.

Abstract estimate of approximate quantities required for the construction of Police lines and quarters at Davangere.

(a) *Quarters for non-Commissioned Officers.*

Sl. No.	Items of work	Per	Rate	Quantity	Tender rate in	
					Words	Figures
			Rs. a. p.			
1	Earthwork excavation	C.yd.	0 4 0	55		
2	Stone jelly concrete in lime mortar ..	C.ft.	0 4 0	380		
3	Size stone in mud	,,	0 4 0	1,203		
4	Burnt brick in mud	,,	0 4 0	1,093		
5	Burnt stone slabs $6\frac{1}{2}$" dressed and fixed in mortar	Sq.ft.	0 6 0	155		
6	Burnt brick in mortar	C.ft.	0 4 6	361		
7	Teakwood doors, battened shutters including bolts, pad-locks, hinges, etc., complete	Sq.ft.	1 8 0	126		
8	Teakwood windows, double shutters glazed inside and panelled shutters outside, including iron bars, hooks, hinges, etc., complete	Sq.ft.	2 0 0	48		
9	Teakwood ventilators with shutters including iron bar etc., complete ..	,,	1 8 0	24		
10	Teakwood wrought and put up including wood oiling	C.ft.	5 0 0	52.51		
11	I Class Mangalore tiled roofing over T. W. reepers 2"×1"	Sqr.	35 0 0	8.94		
12	Ridge tiles set in mortar	R.ft.	0 8 0	27		
13	Mortar bands over roofing (thick) ..	,,	0 8 0	66		
14	Plastering 2 coats of lime mortar ..	Sqr.	3 8 0	26		
15	Cement pointing	,,	4 0 0	2.19		
16	Painting 2 coats of chocolate ..	,,	4 0 0	9.33		
17	Flooring over 3 inches of lime concrete (stone jelly) and $\frac{1}{2}$ inch cement plastering	,,	12 0 0	4.33		
18	Burnt brick in mortar coping 9" thick, including plastering complete	R.ft.	0 8 0	52		
19	Drains	L. S.	..	..		
20	White washing	Sqr.	0 4 0	26		
21	Unforeseen charges	L. S.	..	..		

(b) One block of Six Units.

Sl. No.	Items of work	Unit	Rate	Quantity	Tender rate in	
					Words	Figures
			Rs. a. p.			
1	Earthwork excavation for foundation	C.yd.	0 4 0	161		
2	Stone jelly concrete in lime mortar ..	C.ft.	0 4 0	1,233		
3	Size stone in mud	,,	0 4 0	3,329		
4	Burnt brick in mud	,,	0 4 0	3,929		
5	Burnt brick in chunam mortar ..	,,	0 4 6	499		
6	Burnt stone slabs dressed and fixed in mortar	S.ft.	0 6 0	370		
7	Teakwood doors battened, with shutters, including hinges, bolts, padlocks, etc., complete	S.ft.	1 8 0	306		
8	Teakwood windows with shutters with iron bars, hooks, hinges, etc., complete	S.ft.	2 0 0	105		
9	Teakwood wrought and put up including wood-oiling	C.ft.	5 0 0	137		
10	Plastering with chunam mortar ..	Sqr.	3 8 0	123·67		
11	Whitewashing two coats	Sqr.	0 4 0	123·67		
12	Roofing with first class Mangalore tiles over teak reepers including mailing, etc., complete	Sqr.	35 0 0	25·11		
13	Flooring with 3″ lime concrete and cement plastering $\frac{1}{2}$″ thick ..	Sqr.	12 0 0	14·04		
14	Cement pointing to basement ..	,,	4 0 0	2·42		
15	Brick in mortar coping including plastering	R.ft.	0 8 0	203		
16	Teakwood ornamental finials ..	Each	4 0 0	2		
17	Mortar bands over roof	R.ft.	0 4 0	188		
18	Chocolate painting 2 coats	Sqr.	4 0 0	10·50		
19	Ridge tiles set in mortar	R.ft.	0 8 0	83		
20	Constructing drains, etc., for leading off water	L. S.	..	..		
21	Unforeseen items of work	L. S.	..	..		

R. TIPPAIYA,
Executive Engineer.

MEDICAL DEPARTMENT

VICTORIA, VANI VILAS AND MINTO OPHTHALMIC HOSPITALS, BANGALORE.

Abstract Notification, dated 27th February 1936.

The public are hereby informed that sealed tenders (in triplicate) on half a sheet of foolscap size paper for the supply of bedding and clothing to the Vani Vilas Hospital, Bangalore, will be received at the Office of the Secretary, Victoria, Vani Vilas and Minto Ophthalmic Hospitals (Victoria Hospital) by the undersigned at 11 A.M., on Monday the 30th March 1936.

For details please *vide* page 305, Part VI, of the *Mysore Gazette*, dated 27th February 1936.

C. K. CHELLAPPA IYER,
Secretary,
Victoria, Minto and Vani Vilas Hospitals.